

**CITY OF KIRKLAND**  
**LWHS PED BIKE IMPROVEMENTS**  
**JOB NO: 31-24-PW NO. NMC3000030**  
**ADDENDUM NO. 2**

**TO THE PLANS, SPECIFICATIONS, PROPOSAL, AND CONTRACT**

Issued This Date: July 12, 2024  
Bid Opening: **Unchanged – July 17, 2024**  
Place of Opening: City Hall, Council Chambers, posted online

**Notice to All Plan holders:**

This Addendum No. 2, containing the following revisions, additions, and/or Clarifications, is hereby made part of the Plan and Contract Documents for the above named project. Bidders shall take this Addendum into consideration when preparing and submitting their bids and it shall be attached to the Contract Documents.

Contractors shall acknowledge receipt of this Addendum in the place provided on Proposal Page 6. Failure to do so may disqualify the Bidder from consideration of its bid.

This addendum contains 4 pages, including this page.

All other requirements of the contract documents remain in effect.

---

CONTRACT DOCUMENTS

**ITEM NO. 1: Bid Item Modifications**

Estimated Quantities have been changed for the following Bid Schedule Items to match the Contract details:

- Item No. 47, “Stamped Cement Concrete Pavement” has been added. Quantity and units have been updated to 16 square yards.
- Item No. 50, “Lighting System, NE 80<sup>th</sup> St and 124<sup>th</sup> Ave NE” has been removed.
- Bid item numbers have been revised to reflect changes.

**ITEM NO. 2: Modification of Invitation to Bid**

QUESTIONS AND ANSWERS

**Question 1: The specification Special Provisions 1-02.13 states that irregular proposals will be rejected if WSDOT DBE forms, if applicable, are not submitted. Are there DBE requirements on this project?**

Answer 1: No, there are no DBE requirements for this project.

**Question 2: What color is required for the stamped concrete?**

**CITY OF KIRKLAND  
BID SCHEDULE (Update with project-specific Bid Schedule)**

**LWHS PEDESTRIAN / BICYCLE IMPROVEMENTS  
JOB NO. 31-24-PW**

Note: Unit prices for all items, all extensions, and the total amount of the bid must be shown. All entries must be typed or entered in ink.

<b>Item No.</b>	<b>Item Description</b>	<b>Spec. Ref.</b>	<b>Est. Qty</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Amount</b>
1	Minor Change	1-04	EST	LS		
2	Roadway Surveying	1-05	1	LS		
3	Record Drawings (MINIMUM BID \$2,000 )	1-05	1	LS		
4	SPCC Plan	1-07	1	LS		
5	Mobilization	1-09	1	LS		
6	Project Temporary Traffic Control	1-10	1	LS		
7	Clearing and Grubbing	2-01	1	LS		
8	Removal of Structures and Obstructions	2-02	1	LS		
9	Removal/Abandon Storm System	2-02	1	LS		
10	Asphalt Conc. Pavement Removal	2-02	1220	SY		
11	Cement Conc. Pavement Removal	2-02	40	SY		
12	Roadway Excavation Incl. Haul	2-03	1	LS		
13	Crushed Surface Top Course	4-04	130	TN		
14	HMA CL. 1/2" PG 64-22	5-04	150	TN		
15	Headwall	6-02	1	LS		
16	Solid Wall PVC Storm Sewer Pipe 6 In. Diam.	7-04	30	LF		
17	Solid Wall PVC Storm Sewer Pipe 12 In. Diam.	7-04	610	LF		
18	Solid Wall PVC Storm Sewer Pipe 18 In. Diam.	7-04	250	LF		
19	Catch Basin Type 1	7-05	9	EA		
20	Catch Basin Type 1 Thru Curb	7-05	1	EA		
21	Catch Basin Type 1L	7-05	5	EA		
22	Frame and Vane Grate	7-05	13	EA		
23	Open Curb Face Frame and Grate	7-05	1	EA		

**MUST BE SUBMITTED WITH PROPOSAL**

24	Solid Locking Lid	7-05	2	EA		
25	Conversion Riser	7-05	2	EA		
26	Debris (Bird) Cage	7-05	1	EA		
27	Service Connection 1 In. Diam.	7-15	1	EA		
28	Erosion Control and Water Pollution Prevention	8-01	1	LS		
29	Inlet Protection	8-01	32	EA		
30	Seeding and Fertilizing	8-02	462	SY		
31	Bark Mulch	8-02	6	CY		
32	Fine Compost	8-02	15	CY		
33	Top Soil Type A	8-02	60	CY		
34	Cement Conc. Pedestrian Curb	8-04	160	LF		
35	Cement Conc. Vertical Curb and Gutter Type "A"	8-04	1090	LF		
36	Mountable Cement Conc. Traffic Curb	8-04	90	LF		
37	Potholing	8-05	17	EA		
38	Cement Conc. Driveway Entrance Type 1	8-06	40	SY		
39	Cement Conc. Driveway Entrance	8-06	155	SY		
40	Painting of Curbs	8-07	90	LF		
41	Raised Pavement Markers (Type 2)	8-09	0.10	HUND		
42	Cement Conc. Sidewalk	8-14	345	SY		
43	Cement Conc. Sidewalk W/ Thickened Edge	8-14	85	SY		
44	Cement Conc. Curb Ramp Type Directional	8-14	3	EA		
45	Cement Conc. Curb Ramp Type Parallel	8-14	4	EA		
46	Cement Conc. Curb Ramp Type Perpendicular	8-14	1	EA		
47	Stamped Cement Concrete Pavement	8-14	16	SY		
48	Detectable Warning Surface	8-14	130	SF		
49	Mailbox Relocation	8-18	2	EA		
50	Rectangular Rapid Flashing Beacon (RRFB) System, Complete	8-20	1	LS		
51	Permanent Signage	8-21	1	LS		
52	Plastic Stop Line	8-22	22	LF		
53	Plastic Crosswalk Line	8-22	125	SF		

Answer 2: The stamped cement concrete pavement shall receive antiquing release agent and sealer (including additive) application using Butterfield Color #PT12 Perma-Tique Antiquing Agent – Storm Grey and Butterfield Color Clear-Guard cure and seal or approved equal.

**Question 3: There is a “WA State Sales Tax” line item on the bid proposal. Does this bid follow “Rule 171”?**

Answer: Yes, this bid follows Rule 171.

**Question 4: The Specials in Section 2-02.5 state pay items for “Cement Conc Sidewalk Removal” and “Cement Conc Curb Removal” but no bid items were provided. Please advise.**

Answer 4: The “Cement Conc Sidewalk Removal” and “Cement Conc Curb Removal” were added to Section 2-02.5 in error. These items are not on the bid items list.

**Question 5: There are no bid items for 6” Concrete Sidewalk and “Stamped Concrete Pavement Pattern”. Please provide bid items.**

Answer 5: The bid item for Stamped Concrete Pavement was added as Item No. 47. The 6” Concrete Sidewalk is covered under Item #42: Cement Concrete Sidewalk.

Sincerely,



---

Tiffany Tillison, P.E., Project Engineer



---

Rod Steitzer, P.E., Capital Project  
Manager